



- General Notes
1. ALL HD CONNECTIONS WITH CHAINAGES TO CONNECT TO UNDERGROUND DRAINAGE
  2. RUNNING CHAINAGE OF HD TAKEN FROM NEXT DOWNSTREAM PIT
  3. SUBSURFACE DRAINS TO OUTLET TO DRAINAGE PITS

**SAFETY FIRST**  
SAFETY STARTS WITH YOU

Rev	Amendment	Initials	Date
1	ISSUED FOR COMMENT		13/01/17

**Integra**

1728 Sturt St, Alfredton  
Post Office Box 4226  
Alfredton Victoria 3350  
T: 03 5322 5999 F: 03 5322 5995

Project  
**LUCAS ESTATE  
RESIDENTIAL SUBDIVISION  
STAGE X6  
LUCAS, VIC**

Authority  
Ballarat City Council - (03) 5320 5500

Drawing Title  
**DRAINAGE PLAN**

Status  
**PRELIMINARY  
NOT FOR CONSTRUCTION**

Designer  
S.HOOPER

Checker  
Scale (A1) 1:500 Scale (A3) 1:1000

Verified  
HOR 0 5 10 15 20 25  
VER

Sheet Number  
**4 of 9**

Drawing Number  
**LUX6-CD-004**

Revision  
**1**

PIT SCHEDULE

PIT No.	TYPE	PIT DIMENSIONS			PIT LEVELS		PIT LOCATION		FACE BRG	COMMENTS
		L	W	D	INVERT	TOP	EASTING	NORTHING		
X14e	EP	-	-	-	448.548	-	745623.543	5841443.501	-	-
X14-1	SEP	900	900	1.382	448.740	450.122	745640.628	5841474.202	240°26'08"	PROVIDE STEP IRONS.
X14-2	SEP	900	750	1.184	448.938	450.122	745633.038	5841478.506	60°26'08"	-
X34	Ex JP	-	-	-	448.279	-	745737.932	5841585.478	60°26'35"	-
X35	JP	900	900	1.805	448.462	450.267	745709.534	5841581.587	60°26'35"	PROVIDE STEP IRONS.
X36	SEP	900	900	1.526	448.571	450.097	745695.421	5841570.796	240°26'08"	PROVIDE STEP IRONS.
X36-1	SEP	900	900	1.458	448.635	450.093	745687.767	5841575.138	60°26'08"	PROVIDE STEP IRONS.
X36-2	SEP	900	750	0.740	449.754	450.494	745681.085	5841587.579	150°26'08"	-

NOTE: SETOUT POINT ARE TO CENTRE OF BASE OF PIT

This plan is provided for marketing and information purposes only, it shows design levels only which may change during construction. Builders should check all information prior to the building process. Where discrepancies exist between the plan of subdivision and this plan, the plan of subdivision shall be taken as correct. It is the responsibility of the prospective purchaser to confirm prior to purchase, all lot levels, fill depths and all service locations are correct.