



Whitley County Health Dept Community Environmental Rating Report

Today's Date 10-11-18 Report for Stable Acres (83 Residences)

of non-compliant systems - determined as % 0% unable to determine

of citations = determined as a % 0 % written complaints/ 13 repairs of 16%

Information received from community It is well known that this addition has flooding and high ground water problems, effecting the septic systems.

Physical site assessment Although a recent physical survey was conducted I can't say there is any existing state defined failures. However, it is mine understanding that many septics have been altered without permission since 1972.

Prior testing data Water testing from 2007 shows E coli levels within flooded areas of the addition to be twice to forty times higher than allowed for full body contact.

Written Summary: Prior to this addition being created the Whitley Co. Plan Comm. had concerns about septic system viability in these soils. Combined with the water issues, septics have failed and will continue to fail. Off site drainage of septic effluent is occurring, especially with flooding. Limited lot size inhibits the proper construction of septic repairs. Many septics, I belive, have tiled to the road tiling, then to the county drain to the north.

Overall Assessed Score (1-5): /