



ORDINANCE NO. 2230

**KELLY PARK CROSSING
DEVELOPMENT OF REGIONAL IMPACT**

THIS DEVELOPMENT ORDER IS MADE AND ENTERED INTO AS OF THIS 21ST DAY OF DECEMBER, 2011, BY AND BETWEEN THE CITY OF APOPKA, A POLITICAL SUBDIVISION OF THE STATE OF FLORIDA, WHOSE ADDRESS IS 120 EAST MAIN STREET, APOPKA, FLORIDA, 32703, HEREINAFTER REFERRED TO AS THE "CITY," AND PROJECT ORLANDO, LLC, A FLORIDA LIMITED LIABILITY CORPORATION, WHOSE ADDRESS IS 1900 SUMMIT TOWER BOULEVARD, SUITE 820, ORLANDO, FLORIDA. PROJECT ORLANDO, LLC IS HEREINAFTER REFERRED TO AS THE "APPLICANT."

This Development Order is for the Kelly Park Crossing Development of Regional Impact ("DRI" or "Kelly Park Crossing DRI").

WHEREAS, the Development Order concerns a mixed use project located on approximately 564 acres in the City, as more particularly described on **Exhibit A**, attached hereto and(hereinafter referred to as the "DRI Property"), and

WHEREAS the Applicant for the DRI is Project Orlando, LLC, and for purposes of this Development Order and for Chapter 380, Florida Statutes, Project Orlando, LLC, constitutes the "Developer." The agent for the DRI is Randall C. Morris; and

WHEREAS, the Applicant is desirous of developing the Kelly Park Crossing DRI as a mixed use development consisting of office, retail, light industrial, residential, institutional, hospital, community college, and hotel; and

WHEREAS, the Applicant submitted an Application for Development Approval pursuant to Chapter 380.06, Florida Statutes on December 23, 2010, which was amended by the Response

Janice G. Goebel, City Clerk
City of Apopka
P. O. Box 1229
Apopka, FL 32704-1229

Return to:

to Requests for Additional Information, dated March, 2011, and the Second Response to Requests for Additional Information, dated June, 2011 (collectively, the “ADA”); and

WHEREAS, the ADA was reviewed and approved by the East Central Florida Regional Planning Council (“ECFRPC”) on August 17, 2011, and

WHEREAS, the ADA contained a master plan, identified as Map H herein and attached as **Exhibit B**, which was reviewed simultaneously with the ADA; and

WHEREAS, the ADA was coordinated by the City and the Applicant with the City’s adopted Comprehensive Plan including the Wekiva Parkway Interchange Vision Plan,

WHEREAS, all public hearings as required by Chapter 380.06, Florida Statutes, were duly noticed and held, on November 8, 2011 - Planning Commission, November 16, 2011 - City Council (1st Reading), and December 7, 2011 - City Council (2nd Reading), affording the public and all affected parties an opportunity to be heard and to present evidence;

NOW, THEREFORE, be it resolved by the City Council of the City of Apopka, that based upon the findings of fact and conclusions of law set forth below and subject to the terms and conditions which follow, the ADA for Kelly Park Crossings, including Map H (**Exhibit B**), is hereby approved, pursuant to the provisions of Section 380.06, Florida Statutes, and other applicable state laws and the Comprehensive Plan, codes and ordinances of the City.

FINDINGS OF FACT AND CONCLUSIONS OF LAW

1. The Applicant filed the ADA with the City and with the ECFRPC as well as Department of Community Affairs (now the Department of Economic Opportunity pursuant to Chapter 2011 Laws of Florida, the “Community Planning Act”) and State and Federal agencies and citizen groups as directed by the ECFRPC.

2. The Applicant is the owner of the real property identified herein, or has the authority to file the ADA and is authorized to obtain a development order pursuant to Chapter 380.06, Florida Statutes.
3. The DRI is not located in an area designated as an Area of Critical State Concern;
4. The DRI is consistent with the adopted State Comprehensive Plan.
5. The DRI including the proposed floor area ratios, is consistent with the City Comprehensive Plan.
6. The DRI is consistent with the Land Development Code.
7. The DRI is consistent with the report and recommendations of the ECFRPC submitted pursuant to subsection 380.06(12).

INDEX OF CONDITIONS

1. Application for Development Approval.....	5
2. Project Description.....	5
3. Rezoning.....	7
4. Form Based Code	8
5. Conversion of Uses.....	9
6. Vegetation and Wildlife.....	10
7. Recreation/Parks	14
8. Water Supply and Water Conservation.....	15
9. Wastewater Management.....	17
10. Stormwater Management.....	17
11. Energy & Technology.....	18
12. Solid Waste.....	18
13. Fire, Police, EMS.....	18
14. Affordable Housing.....	18
15. Education.....	19
16. Transportation.....	19
17. Historical and Archaeological Sites.....	37
18. Green Development Standards.....	38
19. Outdoor Lighting.....	38
20. Monitoring Official and Procedures.....	38
21. Phasing and Buildout.....	38
22. Biennial Reporting Requirement.....	39
23. Downzoning Protection.....	40

EXHIBIT LIST

Exhibit A.....	43
Exhibit B.....	44
Exhibit C.....	45

CONDITIONS

1. **Application for Development Approval.** The DRI is approved subject to the following conditions:

- A. The DRI Development Order shall govern the development of the DRI Property.
- B. The Kelly Park Crossing DRI shall be developed in accordance with the information, data, plans and commitments contained in the ADA which includes supplemental information provided in the Responses to Requests for Additional Information all of which are incorporated herein by reference, unless otherwise provided by these recommendations. The final DRI Development Order shall prevail over any conflicting information, data, plan, or commitments. The second response shall prevail over the first response and the first response shall prevail over the original application. For purposes of this condition, the ADA shall consist of the following items:

- a. Application for Development Approval dated December 23, 2010
- b. Responses to Requests for Additional Information #1 dated March 29, 2011
- c. Responses to Requests for Additional Information #2 dated June 10, 2011

2. **Project Description.**

The DRI is designed to be a mixed-use, high density/intensity development centered around the Kelly Park Road interchange of the proposed Wekiva Parkway. As envisioned in the Wekiva Parkway Protection Act (§369.314, Florida Statutes et. seq.) and the City 's Wekiva Parkway Interchange Vision Plan within the City Comprehensive Plan, the DRI Master Development Plan, attached as **Exhibit B**, calls for intense development proximate to the interchange with

densities and intensities decreasing further from the interchange. Mixed use buildings are allowed throughout the DRI except in those areas designated “Neighborhood” as depicted on Map H (Exhibit B).

The development program presented by the Applicant and herein approved includes:

Land Use	Phase 1	Phase 2	Phase 3	Phase 4	Total Development	FAR	Approximate Acres*
Office	100,000 SF	540,000 SF	641,000 SF	639,996 SF	1,920,996 SF	0.4	84.25
Light Industrial	200,000 SF	3,300,000 SF	1,000,000 SF	727,200 SF	5,227,200 SF	0.6	178.00
Retail/Commercial	100,000 SF	450,000 SF	550,000 SF	272,140 SF	1,372,140 SF	0.3	77.00
Community College	130,680 SF	--			130,680 SF	0.3	20.00
Medical	--	250,000 SF	272,720 SF		522,720 SF	0.4	30.00
Residential	300 DU	400 DU	400 DU	450 DU	1,550 DU	10du/ac	58.00
Conservation							*See footnote below.
Parks	40 Acres	33 Acres	20.75 Acres	--	93.75 Acres	15 %	93.75
Institutional	50,000 SF	50,000 SF	60,000 SF	14,240 SF	174,240 SF	0.4	8.00
Hotel	--	100 RMS	100 RMS	200 RMS	400 RMS	0.4	15.00

(* Conservation land use is estimated at 35 to 45 acres and will be identified at the Master Site Plan submittal. Conservation acreage assigned internal to the DRI may result in reduced acreage for those land uses affected by the designation of conservation acreage. The acreage for any land use may be modified and the location of the conservation lands altered without the need for further development-of-regional-impact review if implemented by Condition 5 or 6 contained herein, as applicable. As set forth in Condition 5, designation of conservation lands may also be satisfied through off-site mitigation.)

(*Conservation land use (estimated at 35 to 45 acres) will be revised once the conservation lands are identified at Master Site Plan submittal. The acreage

assigned to lands uses may be increased and the location of the conservation lands altered without the need for further development-of-regional-impact review if implemented by condition 5 contained herein.)

3. **Rezoning.**

- A. The City acknowledges that the development of the DRI Property will occur over time and in phases. The City agrees that due to the size and scope of the proposed development, the duration of the phasing plan, and the uncertainties in the timeframe for construction of the Wekiva Parkway, the Applicant shall be entitled to effect a rezoning for specific parcels or increments of the DRI Property prior to physical development within increment being undertaken (“Incremental Rezoning”). At the time of submittal of an application for the first Incremental Rezoning, the Applicant shall also submit a conceptual rezoning master plan for the entire DRI Property which shall address conceptually the location of the various uses allowed, including common areas and open space, densities and intensities for permitted uses, traffic circulation for internal roadways, all in conformance with Map H (**Exhibit B**) and the ADA. Further refinement and detailing of the conceptual rezoning master plan as well as a demonstration of conformance with the City’s Land Development Code and the Form Based Code shall be demonstrated within each Incremental Rezoning application. Additionally, each Incremental Rezoning applicable to DRI Property located north of Kelly Park Road shall address the feasibility of establishing roadway connections to other properties designated on the Wekiva

Parkway Interchange Vision Plan, and to establish future connection between the DRI and Round Lake Road

B. The DRI Property is currently utilized for agricultural and silvicultural activities. To ensure compatibility between existing and proposed uses, no new or expanded agricultural or silvicultural activity may occur within one hundred (100) feet of those increments of the DRI Property rezoned pursuant to this section.

4. **Form Based Code.** The Applicant shall be subject to the Form-Based Code being developed by the City for all lands within the Wekiva Parkway Interchange Vision Plan. The Form-Based Code shall include a master site plan development option (known as Option “B”) for non-residential development. This Option shall be available for (1) development proposing building(s) exceeding 40,000 gross square feet of floor area for larger-scale commercial, industrial, and institutional uses; and (2). office parks, industrial parks, and retail centers greater than fifteen (15) acres in size, for college campuses (with or without on-site residential housing), hotel convention centers, and hospital campuses greater than eight (8) acres in size. The Option “B” master site plan shall be consistent with the Form-Based Code design standards for this development option. This Option “B” master site plan shall demonstrate compatibility and connectivity with adjacent districts and road systems. The developer requesting an Option “B” master site plan shall demonstrate that average wages and salaries for jobs created by the new development are equal to or greater than the average wages and salaries existing in Apopka at the latest decennial U.S. Census or such other data as may be acceptable to the City.

5. Conversion of Uses.

- A. The Applicant may increase or decrease the amount of a particular land use within the approved development program by using the Equivalency Matrix attached as **Exhibit C**, which is based on equivalent peak hour directional trip ends and is included herein. In order to ensure that a mix of uses is maintained, use of the Equivalency Matrix may increase or decrease the total amount of each land use by no more than the amount provided for in the Land Use Mix Table at **Exhibit C**, and consistent with the substantial deviation criteria identified in Chapter 380.06(19)(b) 1-14, Florida Statutes, unless the Development Order is amended to accommodate such a change. Greater changes than those discussed above shall be considered cumulatively, and shall be subject to normal Development Order amendment processes.
- B. Additionally, changes in land use must address changes to potable water usage and identify if the potable water capacity and allocation under the applicable consumptive use permit are available. Any time the Equivalency Matrix is used, DEO, ECFRPC, the City, Orange County, the FDOT, the SJRWMD, and the School Board of Orange County must be provided notice of the proposal at least thirty (30) days in advance of the change. Use of the Equivalency Matrix will be reported on an individual and cumulative basis and impacts documented in the biennial report. Any future Notice of Proposed Change (“NOPC”) shall incorporate any changes occurring due to the use of the Equivalency matrix.

6. **Vegetation and Wildlife.**

A. **Listed Species.** Site development activities on the Property shall not result in the harming, pursuit or harassment of wildlife species classified as endangered, threatened or a species of special concern ("listed species") in contravention of applicable State or Federal laws. Should such listed species be at any time determined to be nesting or residing on, or otherwise significantly dependent upon the DRI site, the Applicant shall notify FWC, and or FWS, as applicable and to the extent required by laws and regulations, the Applicant shall cease all activities which might negatively affect that individual or population. The Applicant shall provide proper protection, to the satisfaction of all agencies with jurisdiction, as required by statute or regulation. "Harming" and "harassment" as used in this recommendation shall be defined in the same manner as "harm" and "harass" respectively are defined in 50 CFR Section 17.3.

B. **Preserve Areas.** The Applicant may develop the 14 acres, currently designated on Map H (**Exhibit B**) as "preservation", located south of Kelly Park Road, and will establish a preserve for the protection of gopher tortoises, Sherman's fox squirrel and other listed species and indigenous wildlife in the northwest portion of the DRI as provided for in the report and recommendations of the ECFRPC.

Development of the 14-acre area is contingent on other necessary approvals for development (including those identified in this condition) being obtained from the SJRWMD, the U.S. Fish and Wildlife Service, Florida Fish and Wildlife Conservation Commission, and the Department of Environmental Protection, as may be required by law.

Pursuing this option will add an additional 107 acres, less approximately a 300 foot strip along the eastern property boundary to access Ondich Road, to the 31 acre preserve in the northwest portion of the site and allow development of the 14-acre area near the proposed interchange.

As a part of the approval process for the conceptual rezoning master plan referenced in Condition 3 (A), the City and the Applicant shall reach an open space and parks agreement to preserve a minimum of 45 acres to a maximum of 107 acres for a preservation area. This agreement shall consider the appropriate acreage needs for a viable preservation area while also considering the park and open space needs for people who live and work within the Kelly Park DRI . The maximum preservation area obligation by the Applicant is 107 acres. Any acreage above the 45 minimum acres up to the maximum of 107 acres will receive a credit towards 50% of the open space requirements set forth in the Form-Based Code. Any land set aside for the minimum active recreation area shall not qualify as credit.

As an alternative to land preservation internal to the DRI, preservation may be satisfied through off-site preservation if an off-site mitigation program is jointly accepted by the City and FDEP after consultation with the FFWCC.

- C. If a preserve is established, the following principles and guidelines shall be applied via a management plan to be established by the Applicant, reviewed by State permitting agencies, the City, Orange County, and the ECFRPC, as a non-substantial deviation processed as a NOPC. The management plan does not relieve the Applicant of any State or Federal permitting requirements.
- a. The location of the preserve is to include the existing temperate hardwoods and the improved pasture west and north of the temperate hardwoods, in the northern portion of the development (approximately 100 acres).
 - b. Mowing, controlled burning or livestock grazing are to be utilized to maintain vegetation height suitable for gopher tortoises, Sherman's fox squirrels and foraging by sandhill cranes.
 - c. Pines, preferably longleaf pine, are to be planted in low densities to increase plant diversity and structure for nesting for Sherman's fox squirrel. Pines are not to be planted in densities that would impact gopher tortoises.
 - d. Pedestrian trails and trail infrastructure that do not impact listed species are recommended.

- e. The road, currently shown on Map H (**Exhibit B**) shall be relocated such that it does not intersect the temperate hardwood area, but is moved eastward closer to the eastern property line.
- f. Wetland buffers shall be consistent with the requirements of State permitting agencies or the requirements of the City, whichever is more stringent.
- g. Drought tolerant plants adapted to site conditions shall be utilized.
- h. The Applicant shall identify recreation uses that will be allowed in conservation areas.

The Management Plan shall also include the following components:

- i. Provide for management of gopher tortoises consistent with applicable Florida law.
- j. Establish protocols for exotic and nuisance wildlife and plant control.
- k. Establish a bear management plan that provides educational materials for residents regarding deterrent methods to reduce human-bear conflicts, provide for a trash receptacle and dumpster program to manage potential bear and other wildlife intrusion and develop rules or ordinances that require business and residents to secure wildlife attractants to prevent potential conflicts with bears.
- l. Provide for future residents education regarding the purpose and methods of the management plan.
- m. Provide for installation of kestrel nesting boxes at an appropriate density consistent with the known kestrel population on-site, if any.

- n. Provide for the control of feral and free roaming cats to prevent the depredation of Sherman's fox squirrels and other listed species and indigenous wildlife as recommended by the FWC.
- o. Establish wildlife crossings on interior roads to maintain habitat connectivity where appropriate.
- p. Establish conservation easements and adequate funding to secure and manage preserved areas in perpetuity as needed to implement the management plan. Conservation easements will be conveyed to the SJRWMD, the City, Orange County, the Nature Conservancy, or Florida Audubon, or any other conservation organization whose purpose is the management and preservation of lands.
- q. Conduct biennial wildlife surveys to measure the preserve's success and provide for biennial reporting of the implementation and effectiveness of the management plan at the time of the biennial report.
- r. Develop a mechanism to make modifications to the management plan that are approved via permitting with such modifications being reported within the appropriate biennial report.

7. Recreation/Parks

The Applicant and the City shall enter into a binding developer's agreement to address the provision of parks and recreational facilities for the Kelly Park Crossing DRI prior to approval of the first Incremental Rezoning.

8. Water Supply and Water Conservation

- A. The City's consumptive use permit which expires on September 13, 2031, is anticipated to meet the needs of the City's projected population including the development generated by the DRI. However, each phase of the DRI, beyond phase 1 as identified in the Condition 2, Project Description, of this Development Order, shall proceed only upon confirmation of adequate water supply sources to support the development of said phase through the City's consumptive use permit or other sources that are approved by the SJRWMD.

- B. Reasonably available lower-quality sources of water, including storm water, surface water, and reclaimed water, must be distributed for use or used throughout the DRI in place of higher quality water sources according to the SJRWMD rules and applicable state law. Storm water, surface water and reclaimed water shall be maximized as nonpotable water sources for irrigation.

- C. Any wells no longer in use within the DRI boundary shall be properly plugged and abandoned in accordance with SJRWMD rules and regulations. Any change in the use of the wells is subject to SJRWMD's approval of an appropriate CUP consistent with adopted SJRWMD rules.

- D. Each multifamily residential unit subject to an individual deed for property ownership and nonresidential multi-unit structures shall use submeters for potable water. Multifamily residential units not subject to individual deeds shall use master meters.

- E. Development within the Kelly Park Crossing DRI shall comply with applicable provisions of the City's Landscape and Irrigation Ordinance No. 2069.
- F. The covenants, codes and deed restrictions shall require that only U.S. Environmental Protection Agency Water Sense-labeled water-conserving fixtures or equivalent performing fixtures shall be installed in all residential and nonresidential buildings and structures.
- G. The covenants, codes and deed restrictions shall require that only U.S. Environmental Protection Agency Energy Star-labeled water-conserving fixtures or equivalent performing fixtures shall be installed in all residential and nonresidential buildings and structures.
- H. The Applicant shall implement the water conservation practices described in the ADA and subsequent sufficiency responses to maximize water conservation and enhance water quality.
- I. The Applicant shall obtain water from the City subject to the City's rate resolutions and ordinances. The Applicant shall enter into an agreement with the City addressing the timing and funding of potable water and nonpotable water infrastructure projects that are needed to support the DRI.

- J. A distribution system for nonpotable water (i.e., storm water, surface water and reclaimed water) shall be installed concurrently with both residential and nonresidential development within the DRI. The Applicant and the City shall enter into an agreement addressing the timing and funding of the nonpotable water system. The nonpotable distribution system shall be developed parallel to and concurrently with the potable water distribution system for utilization. All irrigation systems installed in the development shall be designed to accept nonpotable water.

9. Wastewater Management.

- A. Development of the DRI shall proceed concurrent with the provision of adequate central sewer service meeting the adopted level of service standards in the City Comprehensive Plan. The Applicant shall enter into an agreement with the City addressing responsibility for the design, construction and funding of central sewer lines to service the DRI.

10. Stormwater Management.

- A. The stormwater management system shall be designed as a stormwater reuse system, when feasible, to maximize the amount of surface water that will be available for irrigation needs throughout the development.
- B. The Applicant will employ best management practices for erosion and turbidity control.
- C. Low Impact Development (LID) techniques are recommended for the stormwater system to the extent allowed by the SJRWMD. Consultation with

the Program for Resource Efficient Communities at the University of Florida's Institute for Food and Agricultural Services is recommended.

D. The Kelly Park Crossing DRI shall comply with applicable provisions of the City's Landscape and Irrigation Ordinance No. 2069.

11. Energy & Technology.

A. Development within the DRI shall comply with the City's natural gas ordinance that is being developed.

12. Solid Waste. Development within the DRI shall occur consistent with the adopted level of service standards for solid waste identified in the City Comprehensive Plan. The handling, storage, transportation and disposal of any hazardous materials within the DRI will comply with local, state, and federal rules, regulations and laws. All users, generators and operators within the DRI property shall be required to adhere to all federal, state and local laws, codes, ordinances, rules and regulations with respect to the use, management and disposal of hazardous waste.

13. Fire, Police, EMS. Police, fire and EMS service will be provided by the City. This condition does not preclude the application of interlocal agreements for mutual support. The Applicant and the City shall enter into a binding developer's agreement to address the provision of fire, police, and EMS services for Kelly Park Crossing DRI, prior to the approval of the first Incremental Rezoning. Fire/Police/EMS Facilities sites constitutes an Institutional use for purposes of the development program at Condition 2.

14. Affordable Housing. The Affordable Housing Analysis prepared for the Kelly Park Crossing DRI ADA using the approved ECFRPC methodology concluded that

affordable housing will be available at the conclusion of Phase 1. Additional studies shall be conducted for all future phases prior to their commencement. If the ECFRPC methodology is applied, compliance with the ECFRPC methodology shall also mean meeting the requirements to appropriately mitigate impacts for each phase as identified in said methodology. The Kelly Park Crossing DRI can mitigate for very low and/or low affordable housing deficiencies with accessory dwelling units only if found by the City to be consistent with existing zoning requirements and supporting land development regulations.

15. Education. The Kelly Park Crossing DRI shall enter an agreement with the Orange County School Board to address school capacity needs created by the DRI.

16. Transportation.

A. The Kelly Park Crossing DRI shall be divided into the following vehicular traffic phases based on reaching any of the following thresholds or years, as indicated below.

Phase & Year	Daily Trips	Daily Trips Cumulative	External* Daily Trips	External* Daily Trips Cumulative	Peak Hour Trips	Peak Hour Trips Cumulative	External* Peak Hour Trips	External* Peak Hour Trips Cumulative
Phase 1 2016	17,907**	17,907	16,121	16,121	1,497	1,497	1,332	1,332
Phase 2 2021	58,868	76,775	46,078	62,199	5,979	7,476	5,089	6,421
Phase 3 2026	40,708	117,483	32,375	94,574	4,215	11,691	3,507	9,928
Phase 4 2031	21,041	138,521	47,388	141,962	2,533	14,224	2,153	12,081

External trips reflect anticipated internalization reductions but not passer-by reductions

** The Kelly Park Crossing phase 1 is constrained by the City’s comprehensive plan which limits the DRI to 7000 total daily trips. However, the applicant’s traffic study confirms that phase 1 can generate up to 17,907 total daily trips. Therefore, the DRI is limited to 7,000 total daily trips until such time as the City’s

comprehensive plan can be amended. If the amendment is approved, phase 1 shall be 17,907 total daily trips without the need to further amend this development order. Mitigation for phase 1 development must be secured by a development agreement prior to commencement of phase 1 development.

Subsequent to phase 1 but prior to the initiation of each phase thereafter as identified in the preceding paragraph, the Applicant shall conduct a monitoring/modeling (M&M) program. This program shall ascertain the Level of Service (“LOS”) on facilities where the Kelly Park Crossing DRI is estimated to contribute an amount of traffic greater than or equal to five percent (5%) of the adopted LOS service volume. The methodology of the M&M program shall be agreed upon by the City, the ECFRPC, Orange County, Lake County, the Florida Department of Transportation (“FDOT”), and the Florida Department of Economic Opportunity and the Applicant. The depth of each M&M effort shall be similar to that required within an ADA (to include all subsequent phases for projected roadway adversity testing) but shall be consistent with the requirements of the City Concurrency Management Systems (if in effect) as it relates to facilities within that jurisdiction. Empirical data will be required to be collected for the M&M program on facilities where it is estimated that the DRI contributes an amount of traffic greater than or equal to five percent (5%) of the adopted LOS maximum service volume. This shall include an origin-destination survey to verify DRI trip distribution on the external roadway network no earlier than seventy-five percent (75%) through any applicable Phase. The origin-destination survey shall also verify the percentage of DRI trips that travel on the Wekiva Parkway. Concurrent with the timing of the origin-destination study, a trip

generation and internal capture study shall be performed to verify trip generation and internal capture assumptions for the development. A trip length study shall also be conducted to verify model results. In the event that all parties cannot come to agreement on the methodology, the ECFRPC, FDOT, the City, Orange County and Lake County shall be the final arbiters. The City's decision shall be final as it relates to its facilities; if required by law, the FDOT's decision shall be final on the strategic intermodal system; Orange County's decision shall be final on Orange County facilities; Lake County's decision shall be final on Lake County facilities; and the ECFRPC's decisions shall be final as it relates to all other facilities. Each M&M program shall provide a roadway needs analysis for each future phase as well as the phase being tested for mitigation requirements.

The facilities to be monitored/modeled for the next phase shall include, but shall not be limited to, those segments of the regional roadways listed below and one segment beyond where the Kelly Park Crossing DRI is estimated to contribute a cumulative amount of traffic 0greater than or equal to five percent (5%) of the adopted LOS service volume. The analyzed facilities will include signalized intersections and link analyses of collector and higher classified roadways and interchange ramps.

The City, the ECFRPC, Orange County, Lake County, FDOT, and DEO shall have the right to make reasonable requests for additional information from the

Applicant to verify adherence to these provisions. The Applicant shall supply adequate information toward compliance with these requirements.

Candidate Roadways for Monitoring and Modeling

Roadway Facility	From	To
US 441	CR 437	Bradshaw Road
SR 46	US 441	CR 437 north
SR 429 (Expressway)	Florida's Turnpike	Apopka Bypass (John Land Expressway)
Wekiva Parkway	SR 429	Interstate 4
CR 435 (Rock Springs Road)	Kelly Park Road	Sandpiper Road
CR 435 (Park Avenue)	Sandpiper Road	Cleveland Street
CR 435 (Clarcona Road)	Cleveland Street	Clarcona-Ocoee Road
CR 437	CR 44A	Orange-Lake County Line
Plymouth – Sorrento Road	Orange-Lake County Line	US 441
Welch Road	Vick Road	Wekiva Springs Road
Binion Road/Orange Avenue	Apopka Ocoee Road	US 441
Errol Parkway	Lake Francis Drive	Lake Arden Drive
Golden Gem Road	Kelly Park Road	Ponkan Road
Haas Road	Plymouth Sorrento Road	Mt. Plymouth Road
Jason Dwelley Parkway	Kelly Park Road	Ponkan Road
Kelly Park Road	Round Lake Road	Rock Springs Road
Lake Francis Drive	Schopke Lester Road	Vick Road
Lester Road	Schopke Road	Plymouth Sorrento Road
Mt. Plymouth Road	Kelly Park Road	Lake County Line
CR 435	Orange County Line	SR 46
Ondich Road	Round Lake Road	Plymouth Sorrento Road
Ponkan Road	Orange Blossom Trail	Rock Springs Road
Round Lake Road	Ponkan Road	Wolf Branch Road
Sadler Avenue	Lake County Line	Orange Blossom Trail
Sadler Avenir/Sadler Road	Orange Blossom Trail	Round Lake Road
Vick Road	Old Dixie Highway	Ponkan Road
Wolf Branch Road	US 441	CR 437
Yothers Road	US 441	Plymouth Sorrento Road

B. The Kelly Park Crossing DRI shall not commence beyond Phase 1 (an equivalent of 1,332 external peak hour trip ends) into Phase 2 or into subsequent phases when service levels are below the minimum service level adopted in the applicable local government's comprehensive plan during the peak hour and if the DRI contributes, or is projected to contribute with the next phase of traffic, five percent (5%) of the adopted LOS service volume of the roadway or intersection unless mitigation measures and/or improvements are secured and committed for completion of construction during the phase in which the impacts occur. This shall be determined by the M&M program required in the preceding condition. The schedule of required roadway improvements shall be tied to the development level when the improvement is needed within each phase. The Development Order shall be amended to incorporate the required improvements and the commensurate trip level by which the improvement is needed to support DRI development.

C. Adequate "secured and committed" mitigation measures shall include one of the following:

- a. A roadway improvement scheduled for construction within the first three (3) years of the appropriate local government's adopted comprehensive plan capital improvement element (or as otherwise provided in the applicable jurisdiction's capital improvement element) or; a roadway improvement scheduled for construction within the first three (3) years of the FDOT's five-year Work Program.

- b. A binding, financially secured and irrevocable commitment by the Applicant or other appropriate persons or entities for the design, engineering, land acquisition and actual construction of the necessary improvements coupled with the posting of a cash bond, surety bond, irrevocable letter of credit, escrow account or other security in a form acceptable to the agency of jurisdiction within the next three (3) years and incorporated by reference into the development order.
 - c. Any other mitigation option specifically provided for in this development order.
 - d. Any other mitigation option permitted by law, including but not limited to a local government development agreement consistent with Chapter 163, Florida Statutes, which ameliorates the projected impact and is incorporated into the DRI Development Order by amendment.
 - e. A proportionate share agreement provided by the Applicant with the City and the jurisdiction or agency whose roadway is impacted, pursuant to Rule 9J-2.045, F.A.C., and Chapter 380.06(15)(e), or Section 163.3180(5)(h)3., Florida Statutes, if applicable at time of agreement.
- D. The above mitigation measures shall occur by the required threshold in order for the DRI to proceed through the balance of the applicable phase. If the Applicant can demonstrate that a portion of a phase does not adversely affect the Regional Roadway network as determined by the M&M tests discussed above, then the Applicant may proceed with that portion of the phase (and only that portion).

- E. In the event that a roadway widening is identified which is not compatible with adopted policy of the FDOT or local government (e.g., constrained), the Applicant, the City, or the party having either maintenance or jurisdictional responsibility for the facility, shall determine alternate mitigation solutions to provide for the movement of people.
- F. Toward the achievement of the objectives in the two preceding conditions, an agreement(s) among the City, Orange County, Lake County, the FDOT, the OOCEA and the Applicant may be created to address and clarify such issues related to equity in the application of collected fees for transportation improvements. In such an event, application of fees shall be applied in a manner consistent with the appropriate rules adopted by the State of Florida or by existing interlocal agreements. However, such an agreement would not alter or waive the provisions and requirements of the other conditions of the Development Order as a mitigative measure for the transportation impacts for the Kelly Park Crossing DRI. In the event that one of the designated parties to the agreement (other than the Applicant) fails to execute said interlocal agreement(s) within the specified time, then the Applicant may proceed with the DRI based upon the modeling M&M schedule and all other recommendations specified herein as it affects the non-participating party. Separate agreements may be entered into with one or more parties and the Applicant.
- G. The following table lists the Phase 1 improvement needs required to mitigate the DRI's intersection impacts during Phase 1. The Applicant shall enter into one or more proportionate share agreement(s) with the City and FDOT, which addresses

the improvement costs, timing of mitigation payments, the option of pipelining proportionate share mitigation fees, and adequate provisions for transportation impact fee credits against proportionate share and mitigation fees. The proportionate share agreements shall be executed prior to any rezoning of the DRI properties.

Phase 1 Intersection Improvement Needs

Roadway/Intersection	Proposed Improvement
SR 46 at CR 437 South	Provide a NB right-turn lane
US 441 at Sadler Avenue	Provide EB and WB left-turn lanes
US 441 at Plymouth-Sorrento Road	Re-stripe to provide an EB and WB auxiliary through lane along US 441. Restripe SB approach to provide an exclusive SB right-turn and shared SB lane for left and right-turns.
Kelly Park Road at Round Lake Road	Add WB right-turn lane.
Kelly Park Road at Plymouth-Sorrento Road	Add EB left-turn lane and re-time signal
Ponkan Road at Plymouth-Sorrento Road	Add NB left-turn lane and re-time signal

H. The following list of improvements has been identified as the result of significant and adverse impacts from the Kelly Park Crossing DRI. It is anticipated that these will be refined by the M&M process prior to each phase. Since widening of

roadways may not be compatible with state and local plans, transit operations or alternate parallel facility improvements should also be considered. A timeframe and responsible party for the implementation of the following improvements, as amended by the M&M program, shall be identified at the beginning of each phase.

Phase 2 (2021)			
Roadway	From	To	Improvement Need
US 441	Yothers Road	Hermit Smith Road	6 Lane Divided
	Plymouth Sorrento Road	Park Avenue	6 Lane Divided
SR 46	Vista View	Round Lake Road	4 Lane Divided
	CR 437 South	CR 437 North	4 Lane Divided
Welch Road	Vick Road	Rock Springs Road	4 Lane Divided
Golden Gem Road	Kelly Park Road	Ponkan Road	4 Lane Divided
Kelly Park Road	Golden Gem Road	Plymouth Sorrento Road	4 Lane Divided
Round Lake Road	Orange County Line	Wolf Branch Road	4 Lane Divided
Phase 3 (2026)			
US 441	SR 19/Duncan Drive	US 19/Bay Street	8 Lane Divided Equivalent
	Donnelly Street	Wolf Branch Road	6 Lane Divided
	Yothers Road	Bradshaw Road	6 Lane Divided
SR 46	US 441	Round Lake Road	4 Lane Divided
	CR 437 South	CR 437 North	4 Lane Divided

SR 429 (Expressway)	Florida's Turnpike	Plant Street	6 Lane Expressway
CR 435/Park Avenue	Orange Street	US 441	6 Lane Divided
CR 435/Clarcona Road	Keene Road	Clarcona-Ocoee Road	4 Lane Divided
Welch Road	Vick Road	Rock Springs Road	4 Lane Divided
Golden Gem Road	Kelly Park Road	Ponkan Road	4 Lane Divided
Kelly Park Road	Golden Gem Road	Jason Dwelley Parkway	4 Lane Divided
Round Lake Road	Orange County Line	Wolf Branch Road	4 Lane Divided
Sadler Road	Lake County Line	Round Tree Road	4 Lane Divided
Vick Road	Welch Road	Lake Francis Drive	4 Lane Divided
Wolf Branch Road	US 441	Britt Road	4 Lane Divided
Phase 4 (2031)			
US 441	CR 473	Old US 441	8 Lane Divided Equivalent
	SR 19/Duncan Drive	Donnelly Street	8 Lane Divided Equivalent
	Donnelly Street	Sadler Road	6 Lane Divided
	Yothers Road	Bradshaw Road	6 Lane Divided
SR 46	US 441	Round Lake Road	4 Lane Divided
	CR 437 South	CR 437 North	4 Lane Divided
SR 429 (Expressway)	Florida's Turnpike	Apopka Bypass	6 Lane Expressway
CR 435/Rock Springs Road	Kelly Park Road	Rock Ridge Boulevard	6 Lane Divided
	Welch Road	Sandpiper Road	6 Lane Divided
CR 435/Park Avenue	US 441	M Gladded Boulevard	4 Lane Divided
CR 435/Clarcona	Cleveland Street	Clarcona-Ocoee Road	4 Lane Divided

Road			
CR 437	SR 44	Orange County Line	4 Lane Divided
Welch Road	Vick Road	Ustler Road	4 Lane Divided
Golden Gem Road	Kelly Park Road	Ponkan Road	4 Lane Divided
Kelly Park Road	Round Lake Road	Jason Dwelley Parkway	4 Lane Divided
Kelly Park Road	Mt. Plymouth- Sorrento Road	Rock Springs Road.	4 Lane Divided
CR 435	Orange County Line	Dubstread Drive	4 Lane Divided
Round Lake Road	Kelly Park Road	Wolf Branch Road	4 Lane Divided
Sadler Road	Lake County Line	Round Tree Road	4 Lane Divided
Vick Road	Welch Road	Lester Road	4 Lane Divided
Wolf Branch Road	US 441	Britt Road	4 Lane Divided

I. If the modeling M&M results as set forth above show that improvements must be made to roadway facilities, and if mitigation is not provided as set forth in these conditions or as otherwise required pursuant to Rule 9J-2.045(7), then prior to any construction of future phases and subject to the provisions of Chapter 380.06(15)(e), Florida Statutes, the Applicant, the City and the entity with jurisdiction over the roadway facility may enter into an agreement which ensures that:

- i. proportionate share payment is made by the Applicant to the appropriate entity(ies) to mitigate DRI impacts; and

- ii. said proportionate share payment shall be used by the appropriate entity only for the design, engineering, right-of-way purchase, permitting and/or construction of improvement to the segments/intersections for which the payment is made; and
- iii. said proportionate share payment by the Applicant constitutes adequate provision for the public facilities needed with respect to the road segments to accommodate the impacts of the DRI through the phase for which the proportionate share was calculated, as required by Chapter 380.15(e)(2), Florida Statutes. All such proportionate share agreements shall be included in this Development Order by amendment pursuant to Chapter 380.06(19), Florida Statutes. The formula to be used to determine proportionate share contribution is as follows:

$$\frac{\text{(DRI Trips)}}{\text{SV Increase}} \times \text{Cost} = \text{Proportionate Share}$$

- iv. For this formula, DRI Trips is the cumulative number of trips from the development expected to reach the roadway during the peak hour from the phase under development. Service Volume (“SV”) increase is the change in peak hour maximum service volume of the roadway resulting from construction of the improvement necessary to maintain the desired level of service; and Cost of Improvement is the cost (at the time of

Applicant's payment) of constructing an improvement necessary to maintain the desired level of service, including all improvement associated costs (engineering design, right-of-way acquisition, planning, engineering, inspection and other associated physical development costs directly required and associated with the construction of the improvement) as determined by the governmental agency having maintenance obligations over the roadway. Transit service and facilities shall be considered in the proportionate share calculations.

- v. Pursuant to COMMUNITY PLANNING ACT OF 2011 (2011-139 F.S.), the proportionate share provisions above shall be reexamined to address the provisions contained therein, and, in the event of a conflict, the Statute shall prevail. Nothing in this development order shall require the Applicant to fund improvements when such funding is inconsistent with the provisions of Florida Statute or Florida Administrative Code. Should an agency disagree with an exemption allowed by the City under this paragraph, the final arbiter on interpreting the Act shall be the DEO.

- J. Notwithstanding any provision contained herein to the contrary, except as specifically agreed to in writing, the City and the entity with jurisdiction over the roadway facility shall have no financial responsibility to contribute to or participate in the funding of the design, engineering, permitting and/or

construction of roadway improvements unless otherwise required to do so by State law.

- K. The M&M required prior to each phase or subphase shall be used to verify impacts from previous phases and to more accurately estimate probable impacts from later phases. The M&M program undertaken prior to Phase 2 shall also assess full buildout. If necessary, the proportionate share amount will be adjusted to reflect actual impacts from a phase and the more accurate information, which will result from the estimates for later phases. If it is verified that the roadway improvements mentioned above are still needed, then the DRI shall not proceed into later phases until either the proportionate share payment is made or the needed improvements are scheduled for construction in the applicable entities' work program within the first three (3) years from the date when impacts are estimated to be significant and adverse. Pursuant to the COMMUNITY PLANNING ACT OF 2011, the requirements above shall be reexamined to address the provisions contained therein. In the event that the Act (COMMUNITY PLANNING ACT OF 2011) addresses the mitigation of transportation impacts in a different manner than those options provided herein, the Applicant may elect to utilize the options afforded by the Act.
- L. Student enrollment for the community college shall initially be limited to 1,866 students. However, if the demand for additional enrollment is established in the future, the conversion matrix may be applied to convert

from another use such that the peak-hour peak-direction trips for the current phase of the Kelly Park DRI are not increased.

- M. The Kelly Park DRI shall not proceed with any portion of the development program that would result in DRI trips above the threshold identified for Phase 1 until the Wekiva Parkway toll facility is constructed and operational. In the event that construction of the Wekiva Parkway is terminated or delayed indefinitely, additional local and state review and approvals will be required for any portion of the DRI beyond Phase 1 to reevaluate impacts and the viability of future development phases.
- N. If the parties cannot reach agreement independently prior to the date when impacts are estimated to be significant and adverse, or if so desired by the parties at any time, then the issues in dispute shall be submitted to the ECFRPC for either voluntary mediation pursuant to its adopted dispute resolution process or to binding arbitration pursuant to the rules and procedures of the American Arbitration Association (“AAA”) unless otherwise agreed by the parties in dispute. The solutions recommended as a result of this process shall be implemented and the Development Order amended pursuant to Chapter 380.06(19), Florida Statutes, to include these solutions.
- O. In order to provide safe access and to preserve operational capacity, the need for deceleration lanes shall be determined by the appropriate permitting agencies and if required, installed by the Applicant. The Applicant and the appropriate permitting agencies shall confirm the need for and the cost of

signalization at the DRI entrances consistent with policies of the City and the appropriate permitting agencies. Signal costs and geometric improvements at DRI entrances are the financial responsibility of the Applicant through DRI buildout unless other traffic warrants such signalization or improvements in advance of DRI demand or other nearby development contributes traffic to the subject intersection, in which case, the Applicant may pay an appropriate fair share for signalization costs as determined by the City.

- P. The development plan will include multiple roadways through the Kelly Park Crossing DRI in order to provide adequate capacity, to provide alternative routes and to lessen the impacts to community cohesiveness.
- Q. To reduce the impacts on arterial roads, the Kelly Park Crossings DRI will include a gridded and connected street network and shall restrict cul du sacs and dead end streets except as may be provided in Condition 4, Option B, of this development order. The DRI will connect to existing and future street networks on and off site when practical as determined by the City in conjunction with Orange County. Nothing in this recommendation is intended to preclude the Applicant from developing a use where a campus is desired without a grid network, or in the event that a grid network would create otherwise unnecessary environmental impacts to wetlands or upland preserve areas.
- R. The Applicant shall cooperate with LYNX to identify the need and confirm the steps necessary to implement the following:
 - i. By Phase 3, identify a potential location for a 200 space park

- and ride lot proximate to the Wekiva Parkway and Kelly Park Road interchange, which may be shared with commercial uses.
- ii. Coordinate with LYNX and Kelly Park Crossing DRI businesses to promote workplace flextime strategies.
 - iii. Reserve sites with adequate size and accessibility for future transit routes, stops and amenities (passenger shelters, transit parking bays and parking spaces for vanpool vehicles) in the development area. During the design, the Applicant shall consult the Lynx Central Florida Mobility Design Manual available at www.golynx.com under publications.
 - iv. Preferential parking for employees who participate in ridesharing programs.
 - v. Financial assistance to provide a route to the site once LYNX and the City determine that ridership levels justify such a connection to the system. Said financial contribution shall be based on a proportionate share of ridership to or from the Kelly Park Crossing DRI, to the extent allowed by law.
 - vi. Coordinate with FDOT's ReThink program (www.rethinkyourcommute.com) in order to increase the modal split of the DRI.
 - vii. Should the Orange Blossom Express (along the US 441 corridor through Apopka) become operational for rail transit, the Applicant shall assess actions to facilitate ridership on the

system, including but not limited to shuttle operations to and from the nearest station during peak traffic hours.

S. In the interest of safety, and to promote alternative forms of transportation, the Applicant shall provide the following bicycle and pedestrian systems:

- i. The on-site bicycle systems shall be connected into any external bicycle systems abutting the Kelly Park Crossing DRI and existing at the time of construction within the DRI, and shall anticipate the connection to the Wekiva Trail.
- ii. Bicycle and pedestrian facilities shall adhere to minimum state standards as contained in the Florida Bicycle Facilities Planning and Design Handbook.
- iii. Provided that there is no conflict with the City's adopted Form Based Code, covered walkways shall be designed into the front of non-residential structures to the maximum extent practicable, but such provision shall not be construed so as to create a mandatory design element, but to create a heightened sensitivity to ensuring cover from the elements for pedestrians.
- iv. In all areas of the Kelly Park Crossing DRI where cycling will be accomplished on both sidewalk/bikeways and streets, appropriate signage identifying bike routes shall be installed.
- v. Special consideration shall be given to bikeways connecting neighboring residential areas to employment and commercial

areas and schools.

- vi. Bicycle support facilities, such as parking racks and/or lockers, shall be provided at commercial areas and work areas.
- vii. DRI roadways and improvements to area roadways approaching the site are recommended to incorporate bicycle and pedestrian facilities.

17. Historical and Archaeological Sites. The Applicant, or any other subsequent developers developing within the DRI, shall notify, or ensure the notification of construction personnel, through posted advisories or other methods, of the potential for artifact discoveries on the Kelly Park Crossing DRI site and to report suspected findings to the DRI manager. In the event of discovery of artifacts of historic or archaeological significance during construction, the Applicant and/or subsequent developers shall immediately halt any construction activity within one hundred fifty (150) feet of the location of any discovery that has the potential to adversely affect the archeological find; and will, within three (3) business days of the discovery of artifacts notify the City and the Division of Historical Resources (“DHR”) of the Florida Department of State. Thereafter, the Applicant will coordinate the evaluation of the artifacts with review agencies and provide any professional assistance necessary to document, relocate, preserve or conserve the site and/or physical artifacts; provide proper protection of the discovery in accordance with applicable law; and provide a written report to the agencies listed above documenting the results of the site evaluation and mitigation/preservation actions proposed or completed. The process and actions described above shall not extend beyond one hundred twenty (120) days to allow evaluation of the site, and, thereafter, the Applicant may continue with development.

18. **Green Development Standards.** The Kelly Park Crossing DRI shall meet the standards of any of the following: the US Green Building Council's (USGBC) Leadership in Energy and Environmental Design (LEED) rating system, the Florida Green Building Coalition (FGBC), the Green Building Initiative's Green Globes program or any other nationally recognized, green building system that is approved by the Department of Management Services (DMS). The Kelly Park Crossing DRI shall at a minimum, meet Energy Star standards for all development.
19. **Outdoor Lighting.** Appropriate "dark skies" measures shall be implemented in all new construction except in areas proximate to the interchange area, provided that acceptable public safety and security are maintained. Actions to direct lights downward and away from existing rural areas may be based upon the Model Lighting Ordinance Users Guide from the Illuminating Engineering Society. These provisions may be accessed at http://docs.darksky.org/MLO/MLO_FINAL_June2011.pdf.
20. **Monitoring Official and Procedures.** The City Administrator, or his or her designee, shall be responsible for monitoring the development and enforcing the provisions of this Development Order. The City shall not issue any permits or approvals or provide any extensions of services if the Applicant fails to comply with this Development Order. This Development Order will be enforced by the City of Apopka through implementation of its adopted Comprehensive Plan, Land Development Code, Code Enforcement by the designated Zoning Official of the City, pursuant to the provisions of Section 380.11, Florida Statutes, or as otherwise provided by law.
21. **Phasing and Buildout.** The Kelly Park Crossing DRI is to be developed as a four-phase project. The projected buildout date for all DRI development is December 31, 2031. The

Applicant shall commence physical development of five percent (5%) of Phase 1 of the DRI (e.g. one hundred seventy-two (172) [residential units, commercial square footage, etc.] or equivalent number of PM peak-hour external trips) within five (5) years after the effective date of this Development Order, otherwise this Development Order shall expire. Should the Applicant donate property to the City for an institutional use (e.g. fire station, police station, City Hall Annex, etc.) the maximum FAR allowed under the adopted comprehensive plan shall be assigned to the parcel and the square footages resulting from this analysis shall be applied to the 5% of phase 1 referenced herein. Alternatively, should the applicant commence construction on the spine road from Kelly Park Crossing to Ondich Road within three years of the effective date of this development order then the five percent threshold shall have been met. The Applicant and the City estimate that approximately twenty (20) years will be required to complete the development described herein.

22. Biennial Reporting Requirement. In accordance with Chapter 380.06(18), Florida Statutes, the Applicant, its successors or assigns, shall submit a biennial report on or before the two year anniversary date of this Development Order and in every other or second year thereafter during the buildout of the DRI (the "Biennial Report"). The Biennial Report shall be submitted to the City, the ECFRPC, the DCA (or successor agency, as applicable), the SJRWMD and all affected agencies formally requesting copies of the same in writing to the Applicant. The contents of the Biennial Report shall comply with the relevant conditions of approval of this Development Order, Chapter 380.06(18), Florida Statutes, Rule 9J-2.025(7), F.A.C, and any and all other and further information required under applicable law. The Biennial Report shall include a statement that all persons/agencies listed above or otherwise entitled to receive the Biennial Report

have been sent copies and the failure to timely submit the Biennial Report may subject the Applicant and the Kelly Park Crossing DRI to the temporary suspension of this Development Order in accordance with Chapter 380.06(18), Florida Statutes. In each biennial report the Applicant shall provide information and documentation as to how and in what manner the DRI is striving to meet and/or is meeting the foregoing energy goals.


23. Downzoning Protection. In accordance with Section 380.06(15), Florida Statutes, the DRI, as approved in this Development Order, shall not be subject to downzoning, unit density reduction, or intensity reduction before December 31, 2031, as such date may be extended, unless the Applicant consents to such change, or the City demonstrates that substantial changes in the conditions underlying the approval of the Development Order have occurred or unless the City demonstrates that the Development Order was based on substantially inaccurate information provided by the Applicant or unless the change is clearly established by the City to be essential to the public health, safety, or welfare.

EFFECTIVE DATE: That this ordinance shall take effect upon passage and adoption.


FIRST READING: November 16, 2011

SECOND READING December 7, 2011


THIRD READING AND ADOPTION: December 21, 2011


John H. Land, Mayor

ATTEST:


Janice G. Goebel, City Clerk

APPROVED AS TO FORM:


Frank C. Kruppenbacher, City Attorney


DULY ADVERTISED FOR PUBLIC HEARING:

August 5, 2011
December 9, 2011



[End of document provisions and City Signatures. Glossary, Exhibits, and Map H to follow]

PROJECT ORLANDO, LLC,
A Florida Limited Liability Corporation

By: 
Randall C. Morris


It's: Agent

STATE OF FLORIDA
COUNTY OF ORANGE

The foregoing instrument was acknowledged before me this 5th day of January,
2012, by Randall C. Morris, as Agent of Project Orlando, LLC, a Florida Limited Liability
Corporation. He is known to me to has produced M620-723-55-253-0 FL Morris
As identification and did not take an oath. 1/erse



Michelle A. Gomez
COMMISSION # DD817671
EXPIRES: AUG. 26, 2012
WWW.AARONNOTARY.COM


Signature of Person Taking Acknowledgement

Print Name: Michelle A. Gomez
Title: Notary Public
Commission No.: DD817671
Commission Expires: August 26, 2012

Glossary of Acronyms Used

AAA	American Arbitration Association
ACOE/USACOE	Army Corps of Engineers
ADA	Application for Development Approval
AM&M	Annual Monitoring & Modeling
BRT	Bus Rapid Transit
CCR	Codes, Covenants and Restrictions
CDD	Community Development District
CSDA	Critical Smoke Dispersal Area
DEO	Department of Economic Opportunity
DHR	Division of Historical Resources
DO	Development Order
DRI	Development of Regional Impact
ECFRPC	East Central Florida Regional Planning Council
ERP	Environmental Review Permit
FAC	Florida Administrative Code
FDEP	Florida Department of Environmental Protection
FDOT	Florida Department of Transportation
FFWCC/FWC	Florida Fish and Wildlife Conservation Commission
FGBC	Florida Green Building Coalition
FIHS	Florida Intrastate Highway System
FLEPPC	Florida Exotic Pest Plant Council
USFWS/FWC	US Fish and Wildlife Service
HMP	Habitat Management Plan
LEED	Leadership in Energy and Environmental Design
LOS	Level of Service

MDA	Master Development Association
M&M	Monitoring & Modeling
MMTD	Multimodal Transit District
MPO	Metropolitan Planning Organization
NOPC	Notification of a Proposed Change
OHW	Ordinary High Water
SFS	Sherman's fox squirrel
SHCA	Strategic Habitat Conservation Area
SJRWMD	St. Johns River Water Management District
SOAR	System Operation Assessment Report
SV	Service Volume
TMDL	Total Maximum Daily Load
TOD	Transit Oriented Development
USFWS/FWS	US Fish and Wildlife Service
USGBC	US Green Building Council

EXHIBIT A
PROPERTY DESCRIPTION

LEGAL DESCRIPTION:**SOUTH PARCEL:**

A TRACT OF LAND LYING IN SECTION 13, TOWNSHIP 20 SOUTH, RANGE 27 EAST BEING THOSE LANDS DESCRIBED IN THE FOLLOWING DOCUMENTS RECORDED IN THE PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA: OFFICIAL RECORDS BOOK 9192, PAGE 3515; OFFICIAL RECORDS BOOK 9022, PAGE 4867; OFFICIAL RECORDS BOOK 7529, PAGE 1955; OFFICIAL RECORDS BOOK 6844, PAGE 562; AND OFFICIAL RECORDS BOOK 9022, PAGE 4561, SAID TRACT OF LAND BEING DESCRIBED AS FOLLOWS:

COMMENCE AT THE NORTHWEST CORNER OF SAID SECTION 13 FOR A POINT OF REFERENCE; THENCE RUN NORTH $89^{\circ}53'56''$ EAST, ALONG THE NORTH LINE OF THE NORTHWEST QUARTER OF SAID SECTION 13, A DISTANCE OF 30.00 FEET TO A POINT LYING ON THE NORTHERLY EXTENSION OF THE EAST RIGHT-OF-WAY LINE OF GOLDEN GEM ROAD, AS DESCRIBED IN OFFICIAL RECORDS BOOK 61, PAGE 315, PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA; THENCE RUN SOUTH $00^{\circ}29'41''$ WEST, ALONG SAID NORTHERLY EXTENSION LINE, 30.00 FEET TO THE POINT OF INTERSECTION OF THE AFORESAID EAST RIGHT-OF-WAY LINE OF GOLDEN GEM ROAD WITH THE SOUTH RIGHT-OF-WAY LINE OF KELLY PARK ROAD, AS DESCRIBED IN DEED BOOK 398, PAGE 190, PUBLIC RECORDS OF ORANGE COUNTY FLORIDA; THENCE RUN NORTH $89^{\circ}53'56''$ EAST, ALONG SAID SOUTH RIGHT-OF-WAY LINE, AND ALSO ALONG THE SOUTH RIGHT-OF-WAY LINE OF KELLY PARK ROAD, AS DEPICTED ON THE MAPS OF ORANGE COUNTY ROAD BOND PROJECT 49E, PAGES 164 THROUGH 172, PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA, A DISTANCE OF 1324.28 FEET TO THE NORTHWEST CORNER OF THE LANDS DESCRIBED IN OFFICIAL RECORDS BOOK 4983, PAGE 3251, PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA; THENCE RUN ALONG THE WESTERLY AND SOUTHERLY LINES OF SAID LANDS DESCRIBED IN OFFICIAL RECORDS BOOK 4983, PAGE 3251 AND ALONG THE SOUTHERLY AND EASTERLY LINES OF THE LANDS DESCRIBED IN OFFICIAL RECORDS BOOK 7106, PAGE 2430 THE FOLLOWING COURSES: SOUTH $00^{\circ}04'09''$ EAST, PARALLEL WITH AND 30.00 FEET EAST OF, BY PERPENDICULAR MEASURE, THE WEST LINE OF THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SAID SECTION 13, A DISTANCE OF 853.18 FEET; THENCE, RUN NORTH $89^{\circ}34'22''$ EAST, PARALLEL WITH THE SOUTH LINE OF NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SAID SECTION 13, A DISTANCE OF 160.19 FEET; THENCE RUN SOUTH $00^{\circ}25'38''$ EAST, 30.00 FEET; THENCE RUN NORTH $89^{\circ}34'22''$ EAST, PARALLEL WITH THE SOUTH LINE OF NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SAID SECTION 13, A DISTANCE OF 476.14 FEET TO THE EAST LINE OF THE WEST ONE-HALF OF THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SAID SECTION 13; THENCE RUN NORTH $00^{\circ}21'13''$ WEST, ALONG THE EAST LINE OF THE WEST ONE-HALF OF THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SAID SECTION 13, A DISTANCE OF 579.56 FEET TO A POINT LYING ON THE SOUTH LINE OF THE NORTH 330.00 FEET OF THE WEST ONE-HALF OF THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SAID SECTION 13; THENCE RUN SOUTH $89^{\circ}53'56''$ WEST, ALONG THE SOUTH LINE OF THE NORTH 330.00 FEET OF THE WEST ONE-HALF OF THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SAID SECTION 13, A DISTANCE OF 66.00 FEET; THENCE RUN NORTH $00^{\circ}21'13''$ WEST, PARALLEL WITH AND 66.00

FEET EAST OF, BY PERPENDICULAR MEASURE, THE EAST LINE OF THE WEST ONE-HALF OF THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SAID SECTION 13, A DISTANCE OF 300.00 FEET TO SAID SOUTH RIGHT-OF-WAY LINE OF KELLY PARK ROAD; THENCE RUN ALONG THE SOUTH RIGHT-OF-WAY LINE OF KELLY PARK ROAD, AS DEPICTED ON THE AFORESAID MAPS OF ORANGE COUNTY ROAD BOND PROJECT 49E, AND AS DESCRIBED IN DEED BOOK 398, PAGE 158, PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA THE FOLLOWING COURSES: NORTH 89°53'56" EAST, 620.35 FEET TO THE POINT OF CURVATURE OF A CURVE CONCAVE NORTHERLY; THENCE RUN EASTERLY ALONG SAID CURVE, HAVING A RADIUS OF 5759.65 FEET, A CENTRAL ANGLE OF 01°04'20", AN ARC LENGTH OF 107.79 FEET, A CHORD LENGTH OF 107.79 FEET, AND A CHORD BEARING OF NORTH 89°21'46" EAST TO THE WEST LINE OF THE NORTHEAST QUARTER OF AFORESAID SECTION 13; THENCE RUN SOUTH 00°38'22" EAST, ALONG THE WEST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 13, A DISTANCE OF 1.01 FEET; THENCE RUN NORTH 88°20'48" EAST, 678.92 FEET TO POINT LYING ON THE EAST LINE OF THE WEST ONE-HALF OF THE NORTHWEST QUARTER OF THE NORTHEAST QUARTER OF SAID SECTION 13; THENCE RUN SOUTH 00°26'23" EAST, ALONG THE EAST LINE OF THE WEST ONE-HALF OF THE NORTHWEST QUARTER OF THE NORTHEAST QUARTER AND ALONG THE EAST LINE OF THE WEST ONE-HALF OF THE SOUTHWEST QUARTER OF THE NORTHEAST QUARTER OF SECTION 13, A DISTANCE OF 2584.29 FEET TO THE NORTH LINE OF THE SOUTHEAST QUARTER OF SAID SECTION 13; THENCE RUN NORTH 89°15'10" EAST, ALONG THE NORTH LINE OF THE SOUTHEAST QUARTER OF SAID SECTION 13, A DISTANCE OF 669.79 FEET TO THE NORTHEAST CORNER OF THE NORTHWEST QUARTER OF SAID SOUTHEAST QUARTER; THENCE RUN SOUTH 00°20'17" EAST, ALONG THE EAST LINE OF THE NORTHWEST QUARTER OF THE SOUTHEAST QUARTER OF SECTION 13, A DISTANCE OF 1344.79 FEET TO THE SOUTHEAST CORNER OF SAID NORTHWEST QUARTER OF THE SOUTHEAST QUARTER; THENCE RUN SOUTH 88°58'18" WEST, ALONG THE SOUTH LINE OF SAID NORTHWEST QUARTER OF THE SOUTHEAST QUARTER, 1332.53 FEET TO THE EAST LINE OF THE SOUTHWEST QUARTER OF SECTION 13; THENCE RUN SOUTH 00°38'22" EAST, ALONG THE EAST LINE OF THE SOUTHWEST QUARTER OF SAID SECTION 13, A DISTANCE OF 1351.30 FEET TO THE SOUTHEAST CORNER OF SAID SOUTHWEST QUARTER; THENCE RUN SOUTH 89°32'06" WEST, ALONG THE SOUTH LINE OF THE SOUTHWEST QUARTER OF SAID SECTION 13, A DISTANCE OF 1356.70 FEET TO THE SOUTHWEST CORNER OF THE SOUTHEAST QUARTER OF THE SOUTHWEST QUARTER OF SECTION 13; THENCE RUN NORTH 00°29'50" WEST, ALONG THE WEST LINE OF THE SOUTHEAST QUARTER OF THE SOUTHWEST QUARTER, AND THE WEST LINE OF THE NORTHEAST QUARTER OF THE SOUTHWEST QUARTER OF SECTION 13, A DISTANCE 2147.97 FEET TO THE NORTH LINE OF THE SOUTH 800.00 FEET OF THE NORTHWEST QUARTER OF THE SOUTHWEST QUARTER OF SAID SECTION 13; THENCE RUN SOUTH 89°23'39" WEST, ALONG THE NORTH LINE OF THE SOUTH 800.00 FEET OF THE NORTHWEST QUARTER OF THE SOUTHWEST QUARTER OF SAID SECTION 13, A DISTANCE OF 1321.35 FEET TO THE AFORESAID EAST RIGHT-OF-WAY LINE OF GOLDEN GEM ROAD; THENCE RUN NORTH 00°21'15" WEST, ALONG SAID EAST RIGHT-OF-WAY LINE, 544.71 FEET; THENCE RUN NORTH 00°29'41" EAST, ALONG SAID EAST RIGHT-OF-WAY LINE 2603.65 FEET TO THE POINT OF BEGINNING.

TOGETHER WITH,

NORTH PARCEL:

A TRACT OF LAND LYING IN SECTIONS 11 AND 12, TOWNSHIP 20 SOUTH, RANGE 27 EAST, BEING THOSE LANDS DESCRIBED IN THE FOLLOWING DOCUMENTS RECORDED IN THE PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA: OFFICIAL RECORDS BOOK 9748, PAGE 6465; OFFICIAL RECORDS BOOK 9022, PAGE 3571; OFFICIAL RECORDS BOOK 9022, PAGE 4722; OFFICIAL RECORDS BOOK 6512, PAGE 3520; AND OFFICIAL RECORDS BOOK 9022, PAGE 4215, SAID TRACT OF LAND BEING DESCRIBED AS FOLLOWS:

COMMENCE AT THE SOUTHEAST CORNER OF SAID SECTION 11 FOR A POINT OF REFERENCE; THENCE RUN NORTH 00°27'50" WEST, ALONG THE EAST LINE OF SAID SECTION 11, A DISTANCE OF 30.00 FEET TO THE NORTH RIGHT-OF-WAY LINE OF KELLY PARK ROAD, AS DESCRIBED IN DEED BOOK 398, PAGE 158, PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA FOR THE POINT OF BEGINNING; THENCE RUN SOUTH 89°12'25" WEST, ALONG SAID NORTH RIGHT-OF-WAY LINE, 1182.82 FEET TO THE WEST LINE OF THE LANDS DESCRIBED IN OFFICIAL RECORDS BOOK 9748, PAGE 6465 AND ALSO THE EAST LINE OF THE LANDS DESCRIBED IN OFFICIAL RECORDS BOOK 7171, PAGE 1402, PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA; THENCE RUN NORTH 00°27'50" WEST, ALONG SAID WEST LINE, 2144.38 FEET TO THE NORTH LINE OF SAID LANDS DESCRIBED IN OFFICIAL RECORDS BOOK 7171, PAGE 1402; THENCE RUN SOUTH 89°12'25" WEST, ALONG SAID NORTH LINE, 406.12 FEET TO A POINT LYING ON THE EAST LINE OF LOT 1, OCB ACRES, ACCORDING TO THE PLAT THEREOF, AS RECORDED IN PLAT BOOK 53, PAGE 82, PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA; THENCE RUN NORTH 00°22'27" WEST, ALONG THE EAST LINE OF SAID LOT 1, A DISTANCE OF 0.41 FEET TO THE NORTHEAST CORNER OF SAID LOT 1; THENCE RUN SOUTH 89°15'33" WEST, ALONG THE NORTH LINE OF SAID LOT 1, A DISTANCE OF 1078.73 FEET TO THE WEST LINE OF THE SOUTHEAST QUARTER OF SAID SECTION 11; THENCE RUN NORTH 00°17'05" WEST, ALONG SAID WEST LINE OF THE SOUTHEAST QUARTER, 498.24 FEET TO THE SOUTHEAST CORNER OF THE NORTHWEST QUARTER OF SAID SECTION 11; THENCE RUN SOUTH 89°30'17" WEST, ALONG THE SOUTH LINE OF THE NORTHWEST QUARTER OF SAID SECTION 11, A DISTANCE OF 1330.44 FEET TO THE SOUTHWEST CORNER OF THE EAST ONE-HALF OF SAID NORTHWEST QUARTER OF SECTION 11; THENCE RUN NORTH 00°07'41" WEST, ALONG THE WEST LINE OF SAID EAST ONE-HALF OF THE NORTHWEST QUARTER, 2239.19 FEET TO A POINT LYING ON THE SOUTH RIGHT-OF-WAY LINE OF ONDICH ROAD, AS DESCRIBED IN DEED BOOK 984, PAGE 314, PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA, SAID POINT ALSO BEING ON A NON-TANGENT CURVE CONCAVE NORTHWESTERLY; THENCE RUN ALONG SAID SOUTH RIGHT-OF-WAY LINE AND ALONG THE SOUTH MAINTAINED RIGHT-OF-WAY LINE OF ONDICH ROAD THE FOLLOWING COURSES: THENCE, FROM A TANGENT BEARING OF NORTH 89°15'33" EAST, RUN NORTHEASTERLY ALONG SAID RIGHT-OF-WAY CURVE, HAVING A RADIUS OF 603.70 FEET, A CENTRAL ANGLE OF 44°59'58", AN ARC LENGTH OF 474.14 FEET, A CHORD LENGTH OF 462.05 FEET, AND A CHORD BEARING OF NORTH 67°23'06" EAST TO THE POINT OF TANGENCY; THENCE RUN NORTH 44°53'07" EAST, 69.20 FEET TO A POINT OF CURVATURE OF A CURVE CONCAVE SOUTHEASTERLY; THENCE, CONTINUING ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE, RUN NORTHEASTERLY ALONG SAID CURVE, HAVING A RADIUS OF 543.70 FEET, A CENTRAL ANGLE OF

45°00'00", AN ARC LENGTH OF 427.02 FEET, A CHORD LENGTH OF 416.13 FEET, AND A CHORD BEARING OF NORTH 67°23'07" EAST TO THE POINT OF TANGENCY; THENCE RUN NORTH 89°53'07" EAST, 462.90 FEET TO THE WEST LINE OF THE NORTHEAST QUARTER OF AFORESAID SECTION 11; THENCE, CONTINUING ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE, RUN NORTH 89°08'52" EAST, PARALLEL WITH AND 30.00 FEET SOUTH OF THE NORTH LINE OF THE NORTHEAST QUARTER OF SAID SECTION 11, A DISTANCE OF 1328.91 FEET TO THE WEST LINE OF THE NORTHEAST QUARTER OF THE NORTHEAST QUARTER OF SAID SECTION 11; THENCE, DEPARTING THE AFORESAID SOUTH MAINTAINED RIGHT-OF-WAY LINE OF ONDICH ROAD, RUN SOUTH 00°22'34" EAST, ALONG THE WEST LINE OF THE NORTHEAST QUARTER OF THE NORTHEAST QUARTER AND THE WEST LINE OF THE SOUTHEAST QUARTER OF THE NORTHEAST QUARTER OF SAID SECTION 11, A DISTANCE OF 1960.23 FEET TO THE NORTHWEST CORNER OF THE SOUTHWEST QUARTER OF THE SOUTHEAST QUARTER OF THE NORTHEAST QUARTER OF SAID SECTION 11, SAID CORNER ALSO LYING ON THE NORTH LINE OF THE LANDS DESCRIBED IN OFFICIAL RECORDS 9022, PAGE 3571, PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA; THENCE RUN ALONG THE NORTH LINE OF SAID LANDS DESCRIBED IN OFFICIAL RECORDS BOOK 9022, PAGE 3571 THE FOLLOWING COURSES: NORTH 89°24'56" EAST, ALONG THE NORTH LINE OF THE SOUTHWEST QUARTER OF THE SOUTHEAST QUARTER OF THE NORTHEAST QUARTER AND ALONG THE NORTH LINE THE SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER OF THE NORTHEAST QUARTER OF SAID SECTION 11, A DISTANCE OF 742.90 FEET; THENCE RUN SOUTH 00°28'01" EAST, 634.56 FEET; THENCE RUN NORTH 89°30'17" EAST, PARALLEL WITH AND 30.00 FEET NORTH OF, BY PERPENDICULAR MEASURE, THE SOUTH LINE OF THE NORTHEAST QUARTER OF SAID SECTION 11, A DISTANCE OF 589.09 FEET TO THE WEST LINE OF THE SOUTHWEST QUARTER OF THE SOUTHWEST QUARTER OF THE NORTHWEST QUARTER OF AFORESAID SECTION 12; THENCE RUN NORTH 89°12'49" EAST, PARALLEL WITH AND 30.00 FEET NORTH OF, BY PERPENDICULAR MEASURE, THE SOUTH LINE OF THE NORTHWEST QUARTER OF SAID SECTION 12, DISTANCE OF 1313.70 FEET TO THE WEST MAINTAINED RIGHT-OF-WAY LINE OF EFFIE DRIVE; THENCE, DEPARTING THE NORTH LINE OF THE LANDS DESCRIBED IN OFFICIAL RECORDS BOOK 9022, PAGE 3571, RUN SOUTH 00°02'47" EAST, ALONG SAID WEST MAINTAINED RIGHT-OF-WAY LINE, 15.00 FEET TO THE NORTH LINE OF THOSE LANDS DESCRIBED IN OFFICIAL RECORDS BOOK 6082, PAGES 1970 THROUGH 1972; THENCE RUN SOUTH 89°12'49" WEST, ALONG SAID NORTH LINE, BEING 15.00 FEET NORTH OF THE NORTH LINE OF THE AFOREMENTIONED SOUTHWEST QUARTER, BY PERPENDICULAR MEASURE, 1313.70 FEET TO THE WEST LINE OF SAID NORTHWEST QUARTER OF SAID SECTION 12; THENCE RUN SOUTH 89°30'17" WEST, PARALLEL WITH AND 15.00 FEET FROM, BY PERPENDICULAR MEASURE, THE NORTH LINE OF THE SOUTHEAST QUARTER OF SECTION 11, A DISTANCE OF 589.09 FEET TO THE WEST LINE OF THE EAST 589.09 FEET OF SAID NORTHEAST QUARTER OF SECTION 11; THENCE RUN SOUTH 00°28'01" EAST, ALONG SAID WEST LINE, ALSO BEING THE WEST LINE OF THE SAID LAND DESCRIBED IN OFFICIAL RECORDS BOOK 6082, PAGES 1970 THROUGH 1972, A DISTANCE OF 15.00 FEET TO THE NORTH LINE OF SAID SOUTHEAST QUARTER OF SAID SECTION 11; THENCE RUN SOUTH 00°27'50" EAST, ALONG SAID DESCRIBED WEST LINE, PARALLEL WITH AND 589.09 FEET FROM, BY PERPENDICULAR MEASURE, THE SAID EAST LINE OF SAID SECTION 11, A DISTANCE OF 1481.61 FEET TO THE SOUTH LINE OF THE NORTH 150.00 FEET OF THE EAST 589.09 FEET OF THE NORTHEAST QUARTER OF THE SOUTHEAST QUARTER OF THE SOUTHEAST

QUARTER OF SAID SECTION 11; THENCE RUN NORTH 89°21'20" EAST, ALONG SAID SOUTH LINE, 589.09 FEET TO THE EAST LINE OF SAID SECTION 11; THENCE RUN SOUTH 00°27'50" EAST, ALONG SAID EAST LINE, 1150.07 FEET TO THE POINT OF BEGINNING.

THE ABOVE DESCRIBED TRACTS OF LAND LIE IN ORANGE COUNTY, FLORIDA AND CONTAIN A COMBINED TOTAL OF 562.836 ACRES, MORE OR LESS.


01-11-12 Project: Orange DMV Restroom 11-12-12 Draft: Kresky Nov 09, 2011 - 8:28 AM

SEE SHEET 1 FOR LEGAL DESCRIPTION SURVEYOR'S NOTES & LEGEND
 SHEET 7 OF 7
 SOUTH PARCELS

DATE	BY	REVISION
11-09-11	TRACY	ISSUE NIGHT BOUNDARY AND LEGAL DESCRIPTION CASE # 11-12-12
11-22-11	TRACY	ISSUE NIGHT BOUNDARY AND LEGAL DESCRIPTION CASE # 11-12-12


MAP OF BOUNDARY SURVEY
 LOCATED IN
 SECTIONS 11, 12 & 13, TOWNSHIP 20 SOUTH, RANGE 27 EAST
 ORANGE COUNTY, FLORIDA

PEC SURVEYING AND MAPPING, LLC
 CERTIFICATE OF AUTHORIZATION NUMBER LP 7808
 207 Alachua Boulevard, Suite 11 • Ocala, Florida 32765 • 352-252-9827




NO.	DESCRIPTION	DATE
1	ADJUSTED	11/09/11
2	ADJUSTED	11/09/11
3	ADJUSTED	11/09/11
4	ADJUSTED	11/09/11
5	ADJUSTED	11/09/11
6	ADJUSTED	11/09/11
7	ADJUSTED	11/09/11
8	ADJUSTED	11/09/11
9	ADJUSTED	11/09/11
10	ADJUSTED	11/09/11
11	ADJUSTED	11/09/11
12	ADJUSTED	11/09/11
13	ADJUSTED	11/09/11
14	ADJUSTED	11/09/11
15	ADJUSTED	11/09/11
16	ADJUSTED	11/09/11
17	ADJUSTED	11/09/11
18	ADJUSTED	11/09/11
19	ADJUSTED	11/09/11
20	ADJUSTED	11/09/11
21	ADJUSTED	11/09/11
22	ADJUSTED	11/09/11
23	ADJUSTED	11/09/11
24	ADJUSTED	11/09/11
25	ADJUSTED	11/09/11
26	ADJUSTED	11/09/11
27	ADJUSTED	11/09/11
28	ADJUSTED	11/09/11
29	ADJUSTED	11/09/11
30	ADJUSTED	11/09/11

NO.	DESCRIPTION	DATE
1	ADJUSTED	11/09/11
2	ADJUSTED	11/09/11
3	ADJUSTED	11/09/11
4	ADJUSTED	11/09/11
5	ADJUSTED	11/09/11
6	ADJUSTED	11/09/11
7	ADJUSTED	11/09/11
8	ADJUSTED	11/09/11
9	ADJUSTED	11/09/11
10	ADJUSTED	11/09/11
11	ADJUSTED	11/09/11
12	ADJUSTED	11/09/11
13	ADJUSTED	11/09/11
14	ADJUSTED	11/09/11
15	ADJUSTED	11/09/11
16	ADJUSTED	11/09/11
17	ADJUSTED	11/09/11
18	ADJUSTED	11/09/11
19	ADJUSTED	11/09/11
20	ADJUSTED	11/09/11
21	ADJUSTED	11/09/11
22	ADJUSTED	11/09/11
23	ADJUSTED	11/09/11
24	ADJUSTED	11/09/11
25	ADJUSTED	11/09/11
26	ADJUSTED	11/09/11
27	ADJUSTED	11/09/11
28	ADJUSTED	11/09/11
29	ADJUSTED	11/09/11
30	ADJUSTED	11/09/11



DATE	BY	REVISION
11-09-11	TRACY	ISSUE NIGHT BOUNDARY AND LEGAL DESCRIPTION CASE # 11-12-12
11-22-11	TRACY	ISSUE NIGHT BOUNDARY AND LEGAL DESCRIPTION CASE # 11-12-12



SEE SHEET 1 FOR LEGAL DESCRIPTION SURVEYOR'S NOTES & LEGEND
 SHEET 3 OF 4
 NORTH PARCEL


MAP OF BOUNDARY SURVEY
 LOCATED IN
 SECTIONS 11, 12 & 13, TOWNSHIP 30 SOUTH, RANGE 27 EAST
 ORANGE COUNTY, FLORIDA

PEC SURVEYING AND MAPPING, LLC
 CERTIFICATE OF AUTHORIZATION NUMBER LB 7208
 300 Alameda Boulevard, Suite 11 • Orlando, Florida 32805 • 407-922-8827

DATE	BY	REVISIONS
11-03-11	TEB	BASE NORTH BOUNDARY AND LEGAL DESCRIPTION (SEE P. 1-12)
8-20-10	TEB	BASE BOUNDARY AND LEGAL DESCRIPTION

NO.	DESCRIPTION	AREA	PERCENTAGE
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50

NO.	DESCRIPTION	AREA	PERCENTAGE
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50



SEE SHEET 2 & 3 FOR "NORTH PARCEL" & "SOUTH PARCEL" AREAS

SHEET 4 OF 4
PERMETER IMPROVEMENT DETAILS
MAP OF BOUNDARY SURVEY
 LOCATED IN
 SECTIONS 12, 13 & 14, TOWNSHIP 20 SOUTH, RANGE 27 EAST
 ORANGE COUNTY, FLORIDA

PEC | SURVEYING AND MAPPING, LLC
 CERTIFICATE OF AUTHORIZATION NUMBER LB 7808
100 Alameda Boulevard, Suite 11 • Orlando, Florida 32805 • 407-941-8907

DATE	BY	REVISIONS

TRACT K BRICK, P&A, R. RES. NO. 8209
 TRACT A WHITE P&A, R. RES. NO. 8214
 DATE: 11/14/11
 DRAWN BY: JLS
 CHECKED BY: JLS
 SCALE: AS SHOWN
 PROJECT NO.: 11-112

EXHIBIT B

MAP H


KELLY PARK CROSSING

City of Apopka, Florida
 DRZ Application for Development Approval


Master Development Plan
 Map N

Legend

- Emergency Only
- Full Access
- Full Access Before Interchange Const
- Right In/Right Out After Interchange Const
- Proposed Walkway Pathway Project
- Proposed Interier Road
- Subject Parcel
- City of Apopka
- Employment
- Interchange
- Neighborhood
- Transition
- Village Center
- Open Space
- Lakes/Rivers



PROJECT TEAM:
 BIO-TECH CONSULTING, INC.
 BEI GROUP, INC.
 IVEY PLANNING GROUP, LLC
 PROFESSIONAL SERVICES INDUSTRIES, INC.
 RM STRATEGIES, LLC
 SMUTTS & BOWEN, LLP
 TRAFFIC PLANNING & DESIGN, INC.



0 1,250 2,500 Feet




EXHIBIT C

LAND USE EQUIVALENCY MATRIX

Holly Park CPO
Land Use Equivalency Matrix

From \ To	Land	Office	Light Industrial	Retail/ Commercial	Community College	Hospital	Medical Office	Residential (Single Family)	Residential (Multi-Family)	Hotel	Institutional	ITE Costs	PM Peak Hour Trip Rates
Office	0.000	1.000	0.200	10.000	0.070	0.410	1.200	2.000	1.714	0.000	710 (6) ¹	1.200 (6)F	
Light Industrial	0.000	0.000	0.700	0.000	0.740	0.331	1.010	1.072	1.300	0.000	110 (6)	0.07 (6)F	
Retail/Commercial	0.000	2.000	3.474	0.000	20.000	2.073	1.100	3.010	0.010	4.014	2.700	0.00 (6) ²	3.37 (6)F
Community College	Students	0.100	0.120	0.000	0.000	0.000	0.001	0.120	0.200	0.171	0.000	0.40 (6) ³	0.12 (6)Student
Medical	Health	1.000	1.300	0.300	10.000	0.000	0.000	1.300	2.700	1.071	1.000	0.10 (6) ⁴	1.31 (6)H
Medical Office	0.000	2.000	3.001	0.000	24.017	2.227	0.000	3.000	3.000	4.000	2.421	730 (6) ⁵	2.00 (6)F
Residential (Single Family)	0.000	0.000	0.000	0.200	0.000	0.700	0.300	0.000	1.000	1.271	0.700	210 (6) ⁶	0.00 (6)F
Residential (Multi-Family)	0.000	0.000	0.000	0.172	4.000	0.440	0.100	0.000	0.000	0.470	0.470	220 (6) ⁷	0.00 (6)F
Hotel	0.000	0.000	0.700	0.200	0.000	0.000	0.200	0.700	1.200	0.000	0.000	330 (6)	0.70 (6)Hotel
Institutional	0.000	1.000	1.200	0.300	10.000	0.000	0.410	1.200	2.000	1.700	0.000	730 (6)	1.21 (6)F

ITE = 1.000 sq ft ITE, ITE = 0.000 sq ft ITE, ITE = 0.000 sq ft ITE
Rates obtained from ITE Trip Generation Report, 6th Edition

Trip generation rates based on total per acre hour trip-generation

1. The equation for Office (710) was used with a site of one half of the total proposed office development (1,000,000 / 2 = 500,000), which yields a rate of 1.200 trips/acre

2. The equation for Shopping Center (000) was used with a site of one half of the total proposed retail development (1,372,140 / 2 = 686,070), which yields a rate of 3.37 trips/acre

3. The rate for Community College (000) is based on the "Student" independent variable in accordance with the trip generation analysis conducted in the traffic study

4. The hospital rate in the development process is a 100-bed hospital totaling 370,000 in size. The rate for Hospital (010) is based on the "Bed" independent variable in accordance with the trip generation analysis in the traffic study

5. The equation for Medical Office (730) was used with a site of one half of the total proposed medical office development (1,470,000 / 2 = 735,000), which yields a rate of 2.00 trips/acre

6. The equation for Single Family Residential (010) was used with a site of one half of the total proposed housing development (200,000 / 2 = 100,000), which yields a rate of 0.00 trips/acre

7. The equation for Multi-Family Residential (020) was used with a site of one half of the total proposed apartment development (1000,000 / 2 = 500,000), which yields a rate of 0.00 trips/acre

Traffic Planning and Design, Inc. (2012)

LAND USE MIX TABLE

LAND USE	MINIMUM	CURRENT	MAXIMUM
Office	1,632,847	1,920,996	2,209,145
Light Industrial	4,443,120	5,227,200	6,011,280
Retail/Commercial	1,312,140	1,372,140	1,432,140
Residential	1,395	1550	1,550